



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

January 7, 1974

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

JAN 10 1974 01-10-74 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Jack Ensminger of L. G. Stephenson has this date requested permission to plug the following described well:

Mr. Ensminger guarantees payment of the plugging fee.

Operator's full Name: L. G. Stephenson

Complete Address: 360 Farm Credit Bank Bldg., Wichita, Kansas

Lease Name: Kepka Well No. 1

Location: NE NE NE Sec. 28 Twp. 14 Rge. 10 (S) (W) X

County: Ellsworth Total Depth 1204' Oil Well Original 2910'

Gas Well Input Well SWD Well D & A Lost Hole X OWWO

Mr. Ensminger was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks cement through

drill pipe at 500'. Pump 25 sacks cement through drill pipe at 250'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,

[Signature] Conservation Division Agent