

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

May 16, 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

RCWD 05-16-82

Dear Sir:

Mr. Larry Hinderliter of Rains & Williamson Oil Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Company, Inc.

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name: Nienke Well No. 1

Location: NW NW SE Sec. 34 Twp. 14 Rge. 9 (E) (W)

County: Ellsworth Total Depth: 3230'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated:

Mr. Hinderliter was instructed to plug the well as follows:

Circulate hole and fill with mud. Pump 50 sacks cement
through drill pipe at 600'. Pump 30 sacks cement through
drill pipe at 200'. Plug and 1/2 sack bulls to be pushed
to 40'. Cement hole to base of cellar with 10 sacks cement.
Cement rat hole with 10 sacks cement.

Very truly yours,

Phillip R. Dick
Conservation Division Agent