

State of Kansas



15-053-20668-00-00

FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

March 11, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co has this

date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Company

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name: Hunter Well No. 2

Location: SE SE SW Sec. 28 Twp. 14 Rge. 9 (E) (W)

County: Ellsworth Total Depth: 3083'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Delaney was instructed to plug the well as follows:

8-5/8" 454'-circulated Hole filled with mud. pump 50 sacks 50-50 Pozmix
w/4% gel and 3% Cal. Chloride through drill pipe at 500'. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Cement rathole with 5 sacks cement.

Very truly yours,


Conservation Division Agent

MAR 16 1981
03-16-81
CONSERVATION DIVISION
Wichita, Kansas