

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 212 W. Park  
 JAN 27 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

January 21, 1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Ehrlich Drilling Company has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Ehrlich Drilling Company & Bob Craig

Complete Address: Wilson, Kansas

Lease Name: Soukup Well No. 1

Location: SW SW SW Sec. 8 Twp. 14 Rge. 9 (E) (W) X

County: Ellsworth Total Depth 2872' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with heavy mud. Push plug and 1/4 sack hulls to 190' and cement

hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
 Conservation Division Agent