



15-053-20515-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

November 29, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC - 6 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. John Armbruster of B+B Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Armbruster guarantees payment of the plugging fee.

Operator's full Name: Davies & Co., Inc.

Complete Address: 1304 Philtower Bldg., Tulsa, Oklahoma

Lease Name: Paul J. Kasper Well No. 1-6

Location: C NE Sec. 6 Twp. 14 Rge. 9 (W)

County: Ellsworth Total Depth 2240' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Armbruster was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe at 500'. Pump 25 sacks cement through drill pipe at 300'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. - Bridge and cement rat hole. 8 3/8" - 309' cement circulated

Very truly yours,


Conservation Division Agent