



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

September 9, 1971

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. W. C. Ogle of Red Tiger Drilling Co. has this

date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: L. V. Stan Bell

Complete Address: Suite 925, 200 W. Douglas, Wichita, Kansas 67202

Lease Name: Zaloudek Well No. 1

Location: NE SE SW Sec. 17 Twp. 14 Rge. 10 (E)(W) X


County: Ellsworth Total Depth 2930' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ogle was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
Conservation Division Agent