

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

May 14, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 16 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Julius Ehrlich of Ehrlich Drilling Company has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Ehrlich Drilling Company

Complete Address: P.O. Box 173, Wilson, Kansas 67490

Lease Name: Sibrava Well No. 2

Location: C E/2 W/2 NE Sec. 17 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 3005' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Ehrlich was instructed to plug the well as follows:

Fill hole with mud. Push plug and 1/4 sack hulls to 220' and cement hole with 25 sacks cement pumped through drill pipe. Push plug and 1/2 sack hulls to 30' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks.

Very truly yours,

[Signature]  
 Conservation Division Agent