

State of Kansas



15-053-30099-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM I. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED April 11, 1966  
STATE CORPORATION COMMISSION

APR 15 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. J. Sullivan of S. and C. Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: S. and C. Drilling, Inc.

Complete Address: P.O. Box 271, Hays, Kansas

Lease Name: Soukup Well No. 1

Location: SE SE NW Sec. 17 Twp. 14 Rge. 10 (E) (W) X

County Ellsworth Total Depth 3300' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

Fill hole with mud to 300'. Push plug and 1/4 sack hulls to 300' and  
cement hole with 25 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent