

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33988
Name: Lebosquet Gas Operations, LLC
Address 1: 535 S. Emporia, Suite 103
Address 2: _____
City: Wichita State: KS. Zip: 67202 + _____
Contact Person: Darrell W. Duncan
Phone: (316) 264-6722
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Chase Group Depth to Top: 2698' Bottom: 2840' T.D. 2901'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 081-21764 · 00 · 00
Spot Description: C NE
SE SE NW NE Sec. 11 Twp. 28 S. R. 33 East West
4320 3986 Feet from North / South Line of Section
4320 1364 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Haskell
Lease Name: Guttridge Well #: 2
Date Well Completed: 12-2008
The plugging proposal was approved on: 09/01/2011 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 09-01-2011
Plugging Completed: 09-06-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	850'	None
		Production	5.5	2898'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1. Set CIBP at 2650' + 2 sxs. cement,
2. RIH w/tubing to 1700', pump 25 sxs. cement.
3. Perforate 875'-unable to pump into.
4. Perforate 862', pump 225 sxs. cement w/o circulation.
5. Top off with 50 sxs. cement.

Plugging Contractor License #: 34082 Name: Alliance Well Service Inc.

Address 1: 470 Yucca Lane Address 2: _____

City: Pratt State: Kansas Zip: 67124

Phone: (620) 672-9100

Name of Party Responsible for Plugging Fees: Lebosquet Gas Operations, LLC.

State of Kansas County, Sedgwick, ss.

DARRELL W. DUNCAN, AGENT Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says; That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so Help me God

Signature: Darrell W. Duncan

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 26 2011

KCC-WICHITA

AP

