

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-169-20,299-0000

LEASE NAME Weller

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Excalibur Production Co., Inc.

SEC. 7 TWP. 15S RGE. 1 (E or W)

ADDRESS P.O. Box 278, McPherson, Kansas 67460

COUNTY Saline

PHONE# (316) 241-1265 OPERATORS LICENSE NO. 5330

Date Well Completed RTD 3-17-89

Character of Well D & A

Plugging Commenced 3-18-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-18-89

The plugging proposal was approved on March 17, 1989 (date)

by Merlan Unruh (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top 2696 Bottom 2699 T.D. 2699

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pushed out
Mississippi	Dry	221	0	8-5/8"	221	0

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1989  
3-27-89  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set. Run drill pipe to 270'. Spot 40 sacks 60/40 Pozmix, 2% Gel. Pull to 60'. Put in plug. Put in 25 sacks cement. Fill to base of collar with cement. Run 1 joint in rathole. Fill with 10 sacks cement. Plugging finished at 4:00 A.M., March 18, 1989.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Tornado Drilling, Inc. License No. 3980

Address P.O. Box 37, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Excalibur Production Co., Inc.

STATE OF Kansas COUNTY OF McPherson, ss.

Terry P. Bandy, Agent

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 37, Canton, Ks. 67428

CYNTHIA G. REIMER  
NOTARY PUBLIC  
STATE OF KANSAS  
MY COM. EXPIRES 6-14-90

CRIBED AND SWORN TO before me this 23rd day of March, 19 89

Cynthia G. Reimer  
Notary Public

My Commission Expires: June 14, 1990

TORNADO DRILLING, INC.  
 P.O. BOX 37  
 CANTON, KANSAS 67428

MARCH 23, 1989

COMPANY: EXCALIBUR PRODUCTION CO., INC.  
 CONTRACTOR: TORNADO DRILLING, INC.  
 FARM: WELLER #1  
 LOCATION: 2970' FSL & 330' FEL SECTION 7-15-1W  
 SALINE COUNTY, KANSAS  
 COMMENCED: MARCH 13, 1989  
 COMPLETED: MARCH 18, 1989  
 ELEVATION: 1282 EST.

0	to	25	Soil & Rock
25	to	200	Lime
200	to	227	Hard (Rock)
227	to	290	Lime
290	to	430	Shale & Lime
430	to	625	Shale & Lime
625	to	780	Shale
780	to	825	Red Beds
825	to	865	Lime
865	to	1305	Lime & Shale
1305	to	1630	Lime & Shale
1630	to	1760	Lime
1760	to	1845	Lime & Shale Sts
1845	to	1880	Douglas
1880	to	1940	Sand
1940	to	2041	Shale (1978 Br Lime)
2041	to	2155	Lansing
2155	to	2325	Lansing-Kansas City
2325	to	2510	Lime & Shale
2510	to	2623	Shale & Lime
2623	to	2696	Shale & Lime
2696	to	2699	Mississippi
		2699	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 27 1989  
 CONSERVATION DIVISION  
 Wichita, Kansas

Drill 12 1/2" hole to 227'. Set 8-5/8" surface casing at 221'. Cement with 150 sacks 60/40 Pozmix, 2% Gel, 3% Cacl. Plug down at 5:45 P.M., March 13, 1989. Well plugged according to the rules and regulations of the State of Kansas, Corporation Commission at 4:00 A.M., March 18, 1989.

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Weller # 1 located on the 2970' FSL & 330' FEL Section 7-15-1W, Saline County, Kansas as is reflected by the files of Tornado Drilling, Inc.

*Terry P. Bandy*  
 Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 23rd day of March, 1989.

*Cynthia G. Reimer*  
 Cynthia G. Reimer - Notary Public

CYNTHIA G. REIMER  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 MY COMM. EXPIRES 6-14-90