

# WELL PLUGGING RECORD

## OR FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Saline County. Sec. 7 Twp. 15S Rge. 1 (E) 1 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4

Lease Owner Phillips Petroleum Company

Lease Name Swan Well No. 1

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-22-1944

Application for plugging filed 6-22-1944

Application for plugging approved 6-22-1944

Plugging commenced 6-22-1944

Plugging completed 6-22-1944

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Rule Durkee

Name of Conservation Agent who supervised plugging of this well Rule Durkee

Producing formation None Depth to top          Bottom          Total Depth of Well 3479 $\frac{1}{2}$  Feet

Show depth and thickness of all water, oil and gas formations.


### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Meisner Sand	Dry	3042'		8 5/8"	130'	None
Hunton	Dry	3050'				
Viola	Dry	3286'				
Arbuckle	Dry	3451'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

Filled with mud from 3479 $\frac{1}{2}$  to 135', set wood plug @ 135' and ran 15 Sax cement. Filled with mud to 20, and set wood plug @ 20' and ran 5 sax cement in filling to base of cellar.



7-14-44

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ralph McKnight

Address Box 528 - Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. Ralph McKnight (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph McKnight

Box 528 - Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 1944

My Commission Expires June 14, 1948

My commission expires         

Robert J. Mason  
Notary Public.

# Formation Record

Lease **Swan**

Well No. **1**

FROM	TO	Formation	REMARKS
0	35	Shale & Shells	<u>Elevation 1247' D. F.</u>
35	85	Sand	
85	140	Lime	
140	340	Lime & Shale	
340	365	Shale, Anhydrite & Red Bed	
365	670	Lime, Sand & Shale	
670	895	Lime & Shale	
895	1180	Lime, Shale & Shells	
1180	1445	Shale & Shells	
1445	1695	Lime & Shale	
1695	1775	Lime	
1775	1910	Lime & Shale	
1910	2055	Shale	
2055	2215	Lime & Shale	
2215	2270	Lime	
2270	2430	Lime & Shale	
2430	2475	Shale	
2475	2605	Lime & Shale	
2605	2660	Shale	
2660	2755	Chat & Shale	
2755	2800	Shale, Chat & Lime	
2800	2850	Chat	
2850	2880	Chat & Shale	
2880	3050	Shale	Top of Meisner Sand 3042' D.F. with no shows.
3050	3180	Lime	Top of Hunten 3050' D.F. with no shows.
3180	3295	Lime & Shale	Top of Viola 3286' D.F. with no shows
3295	3510	Lime, Shale & Chert	
3510	3550	Lime & Chert	
3550	3430	Lime	
3430	3440	Lime & Sand	
3440	3451	Lime, Sand & Shale	Top of Arbuckle 3451' D.F. with no shows
3451	3479½	Lime	Total Depth 3479½' D.F.

7 15-1W  
12-39