

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-20135-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Saline County. Sec. 11 Twp. 15 Rge. 1 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

Lease Owner app. 100' N C W/2 SW NW
Tutcher Oil & Gas Company

Lease Name Peck Well No. 1-A

Office Address Box 308, Overbrook, Ks 66524

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 5-11 1981

Application for plugging filed 5-11 1981

Application for plugging approved 5-11 1981

Plugging commenced 5-11 1981

Plugging completed 5-11 1981

Reason for abandonment of well or producing formation

dry hole

If a producing well is abandoned, date of last production


-- 19--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2600

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	130'	Cemented to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/55 Vis Rotary mud from T.D. up to 150'. Put in plug 1/2 sx hulls and 35 sacks cement. Filled on up w/mud to 40'. Put in plug, 1/2 sx hulls and 10 sx cement. Put 5 sacks in rathole.

RECEIVED
MAY 18 1981
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this report)

Name of Plugging Contractor Berentz Drilling Company

STATE OF Kansas COUNTY OF Greenwood, ss.
Jack Berentz (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 428 Eureka, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of May, 1981

Nancy L. Clark
Notary Public.

My commission expires April 21, 1985

15-169-20135-0000

WELL LOG

OPERATOR Tutcher Oil & Gas

Peck # 1-A

CONTRACTOR Berentz Drilling Co.

760 fsl & 330' fw1

NW/4 Saline County, Ks.

Commenced W/Rotary 5-7-81

Completed W/Rotary 5-11-81

8 5/8" 130' cemented W/65 sacks

Soil	3
Shale & Shells	290
Red Rock	318
Lime	610
Lime & Shale	850
Shale	1158
Lime W/Shale Strks	1252
Shale & Shells	1600
Lime	1685
Shale & Lime	1925
Lime LKC	2231
Shale & Lime	2400
Lime & Shale	2549
Shale	2584
Lime Miss.	2600 RTD

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1981
CONSERVATION DIVISION
Wichita, Kansas