

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-169-20,145-0000

LEASE NAME Robson

WELL NUMBER 1

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 12 TWP. 15 RGE. 1 (K) or (W)

COUNTY Saline

Date Well Completed 8/5/81

Plugging Commenced 10/28/86

Plugging Completed 2/6/87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR B.M. & S. Oil

ADDRESS Box 316 Canton, Kansas 67428

PHONE# (316) 628-4516 OPERATORS LICENSE NO. 5814

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Salina Dist. # 5

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 2639 Bottom 2651 T.D. 2680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi		2639	2651	4 1/2"	2678'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spot twenty-five sacks of cement on bottom through 2" tubing. Leave set for ninety days. Ran Halliburton measuring line to cement at 2320' from surface. Perforate 4 1/2" casing at 250' with five shots. Pump one-hundred-twenty-five sacks of common cement w/Halliburton down casing & back to surface. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor _____ License No. _____

Address _____

STATE OF Kansas COUNTY OF McPherson, ss.

Glen E. McMurry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Glen E. McMurry

(Address) Box 316 - Canton, Kan. 67428

SUBSCRIBED AND SWORN TO before me this 17 day of February, 19 87

STATE CORPORATION COMMISSION Bernhard H. Rundstrom
 Notary Public

My Commission Expires FEB 18 1989 20744-89 **Bernhard H. Rundstrom**

CONSERVATION DIVISION
 Wichita, Kansas
FEB 18 1987
 CONSERVATION DIVISION
 Wichita, Kansas

NOTARY PUBLIC
 McPHERSON COUNTY, KANSAS
 MY APPT. EXP. 3-11-89

JOHNSON JET
SERVICE CO.

Radioactivity Log

COMPANY: WELL: 15/169-2045-0000 FIELD: LOCATION: COUNTY: STATE:	COMPANY: B.M. & S. Oil Canton, Kansas 67428	Well Location
	WELL: Robson # 1	
	FIELD: Sydney H. h. Grove	
	LOCATION: NE SE NE Sec. 12-155-1W	
	COUNTY: Saline STATE: KANSAS	
	LOG ZERO 0=5' A.G.L. DRLG. ZERO PERM. DATUM	ELEV. ELEV. ELEV.

TYPE OF LOG RUN NO. DATE TOTAL DEPTH (DRILLER)	GAMMA RAY Neutron ONE 8-23-81 2665		
TOP OF LOGGED INTERVAL BOTTOM OF LOGGED INTERVAL TYPE OF FLUID IN HOLE FLUID LEVEL	1652 2664 Water Full		
SOURCE STRENGTH & TYPE SOURCE SPACING — IN. LENGTH OF MEAS. DEVICE — IN. O.D. OF INSTRUMENT — IN. TIME CONSTANT — SECONDS LOGGING SPEED FT./MIN.	1 1/4 3 30	AMBE 241 13"	3
RECORDED BY WITNESSED BY	JOHNSON Unruh		

WELL RECORD						
RUN	BIT SIZE	CASING	WT.—LB.	FROM WELL RECORD		FROM LOG
	4 1/2		10 1/2	TO		TO
				TO		TO
				TO		TO
				TO		TO
				TO		TO