


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 12 Twp. 15 Rge. 1 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines. NE NE NE
Lease Owner Fred T. Drolte
Lease Name Robson #1 Well No.
Office Address Amarillo, Texas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 10-20-59 19____
Plugging completed 10-22-59 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2623 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	120'	none
				5-1/2"	2619'	2198'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 2623' and found it open. Filled w/sand to 2610' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing, cleared hole and mudded the hole to 180', set rock bridge to 170' and dumped 25 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECORDED
STATE CORPORATION COMMISSION

NOV 2 1959
11-2-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 59

My commission expires 9-27-62

Thomas V. Dyer
Notary Public.

WELL LOG

15-169-00144-0000

Company: FRED P. DROLTE

Sec. 12 Twp. 15 S Rge. 1W

Farm: ROBSON No. 1

Location: NE NE NE

Saline County, Kansas

Commenced: 4/9/59

Completed: 4/15/59

Total Depth: 2623

Contractor: GREENLAND DRILLING COMPANY

75 SAX pos mix

Casing: 8-5/8" 120'
5-1/2" 2619'

Elevation: 1349 R.B.

Production:

Figures Indicate Bottom of Formations

90	Clay & shale	TOPS:	
120	Line & shale	Brown Line	1940
230	Line & shale	Lansing	1987
600	Line	Cherty Sand	2618
650	Line & shale	RTD	2623
1605	Shale & line		
1825	Line		
1865	Line & shale		
1940	Shale & line		
1943	B. line		
1987	Shale & line		
2310	Line		
2619	Shale & line		
2623	Cherty sand		


HALL, DUKTAN

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Oscar Bridge, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Robson well.


 Oscar Bridge, Vice-President

Subscribed and sworn to before me this 17th day of April, 1959.


 Verdina B. Rutledge, Notary Public

My commission expires March 15, 1960.