

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-169-20,297-0000

LEASE NAME Emig

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630' Ft. from S Section Line

3630' Ft. from E Section Line

LEASE OPERATOR Excalibur Production Co., Inc.

SEC. 14 TWP. 15 RGE. 1W (E) or (W)

ADDRESS Box 278, McPherson, Kansas

COUNTY Saline

PHONE# (316) 241-1265 OPERATORS LICENSE NO. 5330

Date Well Completed 6/21/88

Character of Well Dry

Plugging Commenced 6/16/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/21/88

The plugging proposal was approved on 6/21/88 (date)

by Merlin Unruh, Halstead, Kansas (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Dirt, Clay & Shale		0	50'	8 5/8"	50'	None
Lime & Shale		51'	100'	8 5/8"	50'	None
Shale & lime		101	205'	8 5/8"	105'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Filled hole to 300' with mud & set plug with 50 sacks of cement. Set plug at 60' with 25 sacks of cement, with 10 sacks of cement in rathole. Plugging completed at 6:30 P. M., June 21, 1988 with Merlin Unruh as State Plugging.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Blackstone Drilling, Inc. License No. 5927

Address P.O. Box 1184, McPherson, Kansas 67460

STATE OF Kansas COUNTY OF McPherson, ss.

Charles D. Johnson, Owner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is as follows, that the same are true and correct, so help me God.

(Signature) BY: [Signature]

(Address) P.O. Box 278, McPherson, Ks. 67460

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1988

My Commission Expires: 5/27/92

Notary Public





15-169-20297-0000

Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

June 23, 1988

COMPANY: EXCALIBUR PRODUCTION CO., INC.

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: EMIG #1

LOCATION: 3630' FSL & 3630' FEL
NW SE NW Section 14-15S-1W,
SALINE COUNTY, KANSAS

COMMENCED: June 16, 1988

COMPLETED: June 22, 1988

ELEVATION: 1253 G.L.

0	to	50	Dirt, Clay & Shale
50	to	130	Lime & Shale
100	to	290	Shale & Lime
290	to	1460	Lime & Shale
1460	to	1725	Shale & Lime
1725	to	1951	Lime & Shale
1951	to	2620	Lime
		2620	T. D.

Cut 12½" hole to 203' and run 205' of 8 5/8" casing, cemented with 135 sacks of cement at 203'. Plug down at 9:45 P. M., June 16, 1988. Hole dry and abandoned. Filled hole to 300' with mud & set plug with 50 sacks of cement. Set plug at 60' with 25 sacks of cement, with 10 sacks in rathole. Plugging completed at 6:30 P. M., June 21, 1988 with Merlin Unruh as State Plugger.


TOPS: LANSING - 1911'

Measurements taken from K. B.

JUN 23 1988

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Emig #1, located 3630' FSL & 3630' FEL NW SE NW Section 14-15S-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 23rd day of June, 1988.


JOHNNIE L. SCHMIDT - NOTARY PUBLIC

