

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-169-20,302-0000

LEASE NAME Babe Trillee Farms, Inc.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 21 TWP. 15 RGE. 1 ~~KK~~ or (W)

COUNTY Saline

Date Well Completed RTD 6/7/89

Plugging Commenced 6/7/89

Plugging Completed 6/7/89

LEASE OPERATOR Excalibur Production Co., Inc.

ADDRESS P.O. Box 278, McPherson, Kansas 67460

PHONE#(316) 241-1265 OPERATORS LICENSE NO. 5330

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/7/89 (date)

by Merlan Unruh (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top 2580 Bottom 2597 T.D. 2597

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Dry	200	0	8-5/8	202	0

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1989

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill with mud to 270'. Set plug with 40 sacks cement. Fill with mud to 60'. Set plug with 25 sacks. Fill rat hole with 10 sacks. Plugging complete at 11:00 A.M. June 7, 1989.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Tornado Drilling, Inc. License No. 3890

Address P.O. Box 37, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Excalibur Production Co., Inc.

STATE OF Kansas COUNTY OF McPherson, ss.


Terry P. Bandy

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 37, Canton, Kansas 67428



SUBSCRIBED AND SWORN TO before me this 14th day of June, 1989

Cynthia G. Reimer
Notary Public

My Commission Expires: 6/14/90

15169-2030 2.0000

TORNADO DRILLING, INC.
P.O. BOX 37
CANTON, KANSAS 67428

JUNE 14, 1989

COMPANY: EXCALIBUR PRODUCTION CO., INC.
CONTRACTOR: TORNADO DRILLING, INC.
FARM: BABE TRILLEY FARMS INC. # 1
LOCATION: 2970' FSL & 330' FEL SECTION 21-15-1W
SALINE COUNTY, KANSAS
COMMENCED: JUNE 3, 1989
COMPLETED: JUNE 7, 1989
ELEVATION: 1214 GROUND LEVEL

0	to	25	Soil, Clay, Lime
25	to	100	Hard Lime
100	to	210	Hard Lime
210	to	355	Lime, Sand & Shale
355	to	805	Lime & Shale
805	to	1230	Lime & Shale
1230	to	1585	Shale & Lime
1585	to	1795	Lime & Shale
1795	to	2065	Lime & Shale
2065	to	2290	Lime & Shale
2290	to	2440	Shale & Lime
2440	to	2560	Lime & Shale
2560	to	2580	Lime & Shale
2580	to	2597	Mississippi
		2597	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1989

CONSERVATION DIVISION
Wichita, Kansas


Drill 24 1/2" hole to 230'. Set 8-5/8" surface casing at 200'. Cement with 75 sacks 60/40 Pozmix, 3% CC and 75 sacks of Common Cement. Plug down at 7:45 P.M., June 3, 1989. Drill to Rotary Total depth 2597'. Plug hole. Fill hole with mud to 270. Set plug with 40 sacks. Fill hole with mud to 60'. Set plug with 25 sacks. Fill rat hole with 10 sacks. Rig released at 11:00 A.M., June 7, 1989.

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Babe Trilley Farms, Inc. # 1 located on the 2970' FSL and 330' FEL Section 21-15-1W, Saline County, Kansas as is reflected by the files of Tornado Drilling, Inc.

Terry P. Bandy
Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 14th day of June, 1989.



Cynthia G. Reimer
Cynthia G. Reimer - Notary Public