

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline

County, Sec. 27 Twp. 15 Rge. IV (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE SW NE

Lease Owner Cal Jones

Lease Name Emig Well No. I

Office Address Canton, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 12-20 19 63

Application for plugging filed Nov 19 65

Application for plugging approved Nov 19 65

Plugging commenced II-3 19 65

Plugging completed II-5 19 65

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Gilbert Toman

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 2742' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,473

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2742' to 2595'. Dumped 5 sx of cement. Mudded hole to 160'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bttom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1965
11-17-65
CONS. DIV. WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 th day of November, 19 65.

My commission expires Jan 5, 1966
Notary Public.

WELL RECORD

LEASE: Erig

WELL NO. 1

ELEVATION: 1238 RB

LOCATION: SE SW NE
Sec. 27-15-1W

COMMENCED: 12/20/63

COMPLETED: 12/29/63

OPERATOR: Cal Jones

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, KansasCASING RECORD: 8 5/8" @ 140'/100sx
5 1/2" @ 2606'/25sx

FORMATION	LOG
Shale & Clay	70
Anhydrite	140
Lime & Shale	780
Shale & Shells	1535
Shale & Lime	1865
Lime & Shale	1903
Shale	1938
Lime & Shale	2588
Mississippi	2742
RTD	2742
Sample Tops	
Lansing	1937
Mississippian	2583

FORMATION LOG

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1965
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATE

State of Kansas, County of McPherson, ss.

I, Donald J. Melland, do hereby certify that the above is a true and correct copy of the log of the above named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Donald J. Melland

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas,

this 31st day of December, 1963.

James E. Miller

Notary Public

My Commission expires: August 24, 1967