


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellsworth County, Sec. 8 Twp. 14 Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines SE SW N:
Lease Owner Frankfort Oil Company
Lease Name Kuck Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 30 1955
Application for plugging filed March 30 1955
Application for plugging approved 19
Plugging commenced 19
Plugging completed March 30 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

15 sacks cement @ 270' - filled hole with mud Halliburton plug @ 15'
fill hole with 5 sacks cement.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rine Drilling Company
Address 320 Central Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
J. H. Wilson (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) J. H. Wilson

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1955
(Address) _____
John E. Baker
Notary Public.

My commission expires 6-14-58

PLUGGING
SEC 8 TWP 14 R 10W
PAGE 08 LINE 29

15-053-00113-00-00

SE-04-NE
SEC. 8-14S-10W
ELLSWORTH COUNTY, KANSAS

WELL NO. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY

STARTED: MARCH 5, 1955

COMPLETED: MARCH 31, 1955

	LOG	
CLAY AND SAND	0 - 460	8 5/8" csa @ 319' w/200 sz.
RED IRON AND SHELLS	460 - 970	Syfo @ 390' 1/2", @ 700' 3/4"
SHALE	970 - 1200	
SHALE AND LIME	1200 - 2038	Syfo @ 1300' 1/2", @ 1600' 1/2"
		Syfo @ 2038' 1/2"
SHALE	2038 - 2200	
SHALE AND LIME	2200 - 2795	Syfo @ 2780' 1/2"
LIME	2795 - 2860	
LIME, SAND AND SHALE	2860 - 2965	Syfo @ 2860' 1/2"
LIME AND SHALE	2965 - 3058	
LIME	3058 - 3215	Syfo @ 3063' 1/2"
LIME AND SHALE	3215 - 3285	Syfo @ 3200' 1/2"
LIME, SAND AND CHERT	3285 - 3385	
LIME AND SHALE	3385 - 3425	Syfo @ 3405' 3/4"
LIME AND DOLOMITE	3425 - 3535	
LIME	3535 - 3690	
LIME AND CHERT	3690 - 3780	
DOLOMITE, LIME CHERT, SHALE	3780 - 3800	Syfo @ 3880' 3/4"
LIME	3800 - 3945	Syfo @ 3875' 1/2", @ 3939' 1/2"
DOLOMITE AND SAND	3945 - 4025	Syfo @ 3950' 1/2"
DOLOMITE, SAND AND SHALE	4025 - 4115	Syfo @ 4081' 3/4"
SAND, SHALE AND GRANITE WASH	4115 - 4315	Syfo @ 4130' 1/2"
GRANITE WASH	4315 - 4570	Syfo @ 4130' 1/2"
GRANITE		Syfo @ 4424' 5 1/2", @ 4450' 6"
		Syfo @ 4473' 6 1/2", @ 4488' 6"
		Syfo @ 4700' 6"
		D AND A @ 4570'

STATE OF KANSAS)
COUNTY OF BERNICK) ss.

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE RUCK WELL No. 1, LOCATED IN SE-04-NE, SECTION 8-14S-10W, ELLSWORTH COUNTY KANSAS

R. M. Green
ASST. SECRETARY AND TREASURER

SUBSCRIBED TO AND SWORN BEFORE ME THIS 20TH DAY OF APRIL, 1955

Lois E. Lake
NOTARY PUBLIC

MY COMMISSION EXPIRES 6-14-58

PLUGGING
FILE SEC 8 T 14 S 10W
WELL PAGE 108 LINE 29