


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Saline County, Sec. 28, Twp. 15, Rge. 1W (E) (W)  
Location as "NE/CNWSW" or footage from lines SW/4 SW/4 SW/4  
Lease Owner Excalibur Prod Inc.  
Lease Name Peterson-Wheatley Well No. 1  
Office Address Bx 231 Mc Pherson, Kansas 67460  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 6-22 1964  
Application for plugging filed Dec 1968  
Application for plugging approved Dec 1968  
Plugging commenced Jan 3 1969  
Plugging completed Jan 7 1969  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tooman  
Producing formation Depth to top Bottom Total Depth of Well 2657' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2		2,314'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 2657' to 2640'. Dumped 5 ax of cement. Mudded hole to 160'. Made 10' of rock bridge. Dumped 25 ax of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 ax of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF RENO, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 19 69

My commission expires January 5, 1970

Judy Lamb  
Notary Public.

# Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

June 25, 1964

15-169-19038-0000

COMPANY: JOHNSON-POUFFE  
CONTRACTOR: BLACKSTONE DRILLING, INC.  
FARM: PETERSON-WHEATLEY #1  
LOCATION: SW/4 SW/4 SW/4, Sec. 28-15-1W,  
Saline County, Kansas  
COMMENCED: June 17, 1964  
COMPLETED: June 22, 1964  
ELEVATION: 1273 K.B.

0	to	125	Shale & Lime
125	to	360	Lime
360	to	420	Lime & Shale
420	to	1505	Shale & Lime
1505	to	1725	Lime
1725	to	2003	Shale & Lime
2003	to	2110	Lansing
2110	to	2370	Lime
2370	to	2495	Lime & Shale
2495	to	2652	Shale & Lime
2652	to	2657	Mississippi
		2657	T. D.

Cut 12 1/4 in. hole to 125 ft. and run 126 ft. of 8 5/8 in. surface pipe and cemented on bottom at 125 ft. with 90 sacks cement. Plug down at 12:00 P.M., June 17, 1964.  
Cut 7 7/8 in. hole to 2657 ft. and run 2660 ft. of 5 1/2 in. casing, and cemented at 2652.50 ft. with 50 sacks cement. Plug down at 7:00 A.M., June 22, 1964.

TOPS: Browns Line - 1943' Lansing - 2003' Mississippi - 2652'

Measurements taken from K.B.

## CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Peterson-Wheatley #1, located on the SW/4 SW/4 SW/4 of Sec. 28-15-1W, Saline County, Kansas as reflected by the files of the Blackstone Drilling, Inc.

  
H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas, this 25<sup>th</sup> day of June, 1964.

  
Ruth McVay - Notary Public

MY COMMISSION EXPIRES: Dec. 18, 1965.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas