

WELL PLUGGING RECORD

15-169-00240-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
311 No. Broadway  
Wichita, Kansas

Saline County, Sec. 28 Twp. 15 Rge. 1 (E) (W) X

Location as "NE/CNWxSWx" or footage from lines NE/4 NE/4 NW/4

Lease Owner Johnson-Plouffe

Lease Name Knopf Well No. 1

Office Address Box # 231, McPherson, Kansas - 67460

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed April 10, 1964

Application for plugging filed April 10, 1964

Application for plugging approved 19


Plugging commenced 19

Plugging completed April 10, 1964

Reason for abandonment of well or producing formation Hole Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Cecil Jones, McPherson, Kansas - 67460

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	40			
Shale		40	70			
X <sup>H</sup> Lime		70	132	8 5/8"	132'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 125 ft. with 20 sacks cement. Top plug set at 40 ft. with 10 sacks. 2 sacks in rathole. Plugging completed at 3:00 A.M., April 10, 1964 by Cecil Jones, State Pluggger, McPherson, Kansas.

RECEIVED  
STATE CORPORATION COMMISSION

APR 16 1964

4-16-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.

Address Box # 455, McPherson, Kansas - 67460

STATE OF Kansas COUNTY OF McPherson ss.

Charles D. Johnson & H. J. Plouffe (operator) of the above-described

well, being first duly sworn on oath, says: That we have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help US God.

(Signature)

Box # 231, McPherson, Kansas - 67460

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1964

My commission expires Aug. 27, 1967

Notary Public.


**Blackstone Drilling, Inc.**

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

April 6<sup>th</sup>, 1964**RECEIVED**  
STATE CORPORATION COMMISSION

APR 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: JOHNSON-PLOUFFE  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: KNOFF #1  
 LOCATION: NE/4 NE/4 <sup>NW</sup> SW/4, Sec. 28-15-1W,  
 Saline County, Kansas  
 COMMENCED: April 4, 1964  
 COMPLETED: April 10, 1964  
 ELEVATION: 1228 K.B.

0	to	40	Sand
40	to	70	Shale
70	to	340	Line
340	to	985	Line & Shale
985	to	1945	Shale & Line
1945	to	2227	Line
2227	to	2370	Line & Shale
2370	to	2585	Shale & Line
2585	to	2610	Line & Shale
2610	to	2627	Mississippi
		2627	T. D.

Cut 12 1/4 in. hole to 132 ft. and run 134 feet of 8 5/8 in. surface pipe and cemented with 90 sacks cement and 1 1/2 calcium chloride on bottom at 132 ft. Plug down at 1:15 P.M., April 4, 1964. Cut 7 7/8 in. hole to 2627 feet. Hole dry and abandoned. Bottom plug set at 125 ft. with 20 sacks. Top plug set at 40 ft. with 10 sacks. 2 sacks in rat-hole. Hole plugging completed at 3:00 A.M., April 10, 1964, Cecil Jones, State Plugger, McPherson, Kansas.

TOPS: Brown Line - 1889'      Kansas City - 1950'      Mississippi - 2610'

Measurements taken from K. B.

**CERTIFICATE**

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Knopf #1, located on the NE/4 NE/4 NW/4 of Sec. 28-15-1W, Saline, County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas, this 15<sup>th</sup> day of April 14, 1964.

  
 Ruth McVay - Notary Public

My Commission Expires: December 18, 1965.