

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Saline County. Sec. 29 Twp. 5 Rge. 1 (E) (W)

Location as "NE¼NW¼SW¼" or footage from lines S. W. Cor. S. W. Quarter

Lease Owner. Rocket Drilling Company

Lease Name. King Well No. 1

Office Address. Box 620 McPherson, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole)

Date, well completed. 4-19-41 193

Application for plugging filed. 4-23-41 193

Application for plugging approved. 4-23-41 193

Plugging Commenced. 4-24-41 193

Plugging Completed. 4-26-41 193

Reason for abandonment of well or producing formation

Hole full water

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. Paul Durkey

Producing formation. None Depth to top Bottom Total Depth of Well. 2723 Feet.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8" OD	102	None
				5 1/2" OD	2701	2400

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud 2723-2700'
Cement (6 sax) from 2700-2660
Filled with mud from 2660-200'
Cement plug (10 sax) 200-175'
Filled with mud from 175-14'
Cap (4 sax) cement from 14' to cellar base

PLUGGING
FILE NO. 29-15-21W
BOOK 34 PAGE 31

5-10-41
MAY 1 1941
STATE CORP. COM.
CONSERV. DIV.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Rocket Drilling Company
Address. Box 620 McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Herbert Rhoton (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert Rhoton

(Address)

SUBSCRIBED AND SWORN to before me this 9 day of May, 1941

My commission expires January 7, 1942

Notary Public.

15-169-00057-0000

ROCKET DRILLING COMPANY

Well Log

King # 1
29-15-1W
Saline County,
Kansas

Started spudding April 6, 1941

0	20	Surface Clay
20	40	Rock
40	77	Rock and shale
77	92	Sand
92	115	Lime
	8 5/8" 114' cemented Cement circulated	
115	190	Lime
190	310	Broken Lime
310	378	Red bed and shale
378	405	Anhydriate
405	520	Broken lime
520	534	Sand (rough)
534	562	Broken sandy lime
562	635	Lime and shale
635	730	Lime
730	1655	Shale and shells
1655	1692	Broken lime
1692	1806	Lime
1806	1840	Shale
1840	2037	Lime and shale
2037	2050	Lime
2050	2102	Broken lime
2102	2120	Lime
2120	2155	Lime soft
2155	2175	Lime
2175	2202	Shale
2202	2290	Lime
2290	2595	Shale and shells
2595	2616	Shale
2616	2618	Chert
2618	2635	Shale
2635	2670	Shale and shells
2670	2673	Conglomerate sandy
2673	2674	Chat and lime
2674	2696	Broken lime
2696	2723	Chat
		odor and slight saturation 2703 to 2709'

Ran 5 1/2" OD casing and set at 2701
cemented with 50 sax Oil Max
Cement April 15, 1941
Drilled cement plug April 19, 1941
Hole filled immediately with water, no oil showing
Pulled pipe and plugged April 26, 1941