

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22815-00-00
Spot: E2NWNENE Sec/Twnshp/Rge: 34-10S-20W
4893 feet from S Section Line, 805 feet from E Section Line
Lease Name: TOWNS Well #: 3
County: ROOKS Total Vertical Depth: 3799 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	247	0	200 SX
PROD	4.5	3708	0	100 SX

Well Type: SWE UIC Docket No: D24457.0 Date/Time to Plug: 09/09/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 625 sxs 60/40 pozmix - 4% gel - 500# hulls.
Tubing and packer stuck in the hole at 2599'.
DV at 1544' w/440 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2011 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2566' - pumped 150 sxs 60/40 pozmix - 4% gel with 350# hulls -
circulated cement to surface.
Pulled all tubing. Hooked to 4 1/2" casing - pumped 40 sxs 60/40 pozmix - 4% gel.
Pressured to 700#.
8 5/8" x 4 1/2" annulus. Visually checked cement to surface.

Perfs:

Top	Bot	Thru	Comments
3708	3755		ARBUCKLE

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

SEP 14 2011

Form GP-2/3

cc to WIC 9/23/11