

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25043-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 14-20S-13W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: COOPER-GAUNT Well #: 1-14
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	325	0	300 SX CMT.
TI	2.375	3550		
PROD	4.5	3596	2135	125 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2011 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/08/2011 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
All cement pumped with 2% c.c.
Cut casing at 2135' - pulled casing to 1550' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 700' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 315' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 150' - circulated cement with 55 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3488	3492		

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

9/27/11