

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24920-00-00  
Spot: NWNESWSE Sec/Twnshp/Rge: 19-20S-12W  
1170 feet from S Section Line, 1840 feet from E Section Line  
Lease Name: HADDON FISCHER Well #: 1-19  
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	312	0	300 SX CMT.
T1	2.375	3450		
PROD	5.5	3600	2135	150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/07/2011 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500#hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/07/2011 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.  
All cement pumped with 2% c.c.  
Cut casing at 2135' - pulled casing to 1550' - pumped 125 sxs cement with 300# hulls.  
Pulled casing to 700' - pumped 40 sxs cement with 100# hulls.  
Pulled casing to 315' - pumped 40 sxs cement with 100# hulls.  
Pulled casing to 150' - circulated cement with 55 sxs cement.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3388	3391		
3365	3370		
3330	3334		
3269	3274		

RECEIVED  
SEP 23 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

em

9/27/11