

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-169-20,254-0000

SE, Sec. 7, T 15 S, R 1 W 2

1650 feet from ~~W~~(S) section line

330 feet from ~~W~~(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5606

Lease Name Gillmore Well # 1-7

Operator: R. J. Walker Oil Co., Inc.  
Name & Address 3535 N.W. 58th, Suite 1000  
Oklahoma City, OKla 73112

County Saline

Well Total Depth 2800 feet 91.00

Conductor Pipe: Size feet

Surface Casing: Size 8 3/8 feet 213

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Kansas Drilling & Well Service License Number 5133

Address Marion, Kansas 66861

Company to plug at: Hour: 9:00 AM Day: 29 Month: July Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO D. McDonald

(company name) Kansas Drilling & Well Service (phone) 316 382 2665

were: Fill hole with heavy mud. Pump 45 sacks cement through  
drill pipe at 300'. Fill hole with mud to 40'. Push plug and 1/2  
sack hulls to 40' and cap hole with 11 sacks cement.  
Cement Mouschale with 10 sacks Cement Rathole with 10 sacks

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 AM Day: 29 Month: July Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with heavy mud. 45 sacks cement  
pumped through drill pipe at 300'. Hole Filled with mud to  
40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented  
to base of cellar with 11 sacks cement.  
Mouschale cemented with 10 sacks. Rathole cemented with 10 sacks

Remarks: Completed in Miss. Chat.  
Halliburton Ticket # 748997

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 07 1984  
8-7-84  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ did not) observe this plugging.

Signed [Signature]  
(TECHNICIAN)

INVOICED

DATE 8-13-84

INV. NO. 3006

7-29