

5 030264

FEB 6 1987

API NUMBER 15-169-20,45-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE/4, SEC. 12, T. 15 S, R. 1 (W) E

3630 feet from N/S section line

330 feet from E/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5814

Lease Name Robson Well # 1

Operator: B. M. + S. Oil

County Saline 86.94

Name & Address Bob 316

Well Total Depth 2675 feet

Center, Kansas

Conductor Pipe: Size _____ feet

67428

Surface Casing: Size 8 7/8 feet 160

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor _____ License Number _____

Address _____

Company to plug at: Hour: 10 AM Day: 28 Month: October Year: 1986

Plugging proposal received from Elmer U Ruk

(company name) B. M. + S. Oil (phone) 316 628-4516

were: Pull Rods + Pump. Dump 25 aka Cement Slurry down 2" tubing, follow w/ 8 BBLs water, pull tubing measure cement top. Perf casing @ 250' circulate cement down 4 1/2 casing out 8 7/8 surface casing. Cut pipe off 5' below ground level. No pipe recovery

Plugging Proposal Received by Mesher Uruk (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part Bottom ck top None _____

Operations Completed: Hour: 2 pm Day: 6 Month: Feb Year: 1987

ACTUAL PLUGGING REPORT Pulled Rods, Dumped 25 aka Cmk Slurry, down 2" tubing, pulled tubing. measured top of Cement w/ steel measuring line @ 1935'. Perforated 4 1/2 casing @ 250', circulated 125 aka Cmt down 4 1/2 casing out 8 7/8 surface casing. No pipe recovery.

Waved # 361653-6

Remarks: Checked top plug 2/9/87 - full - cut off + level location (if additional description is necessary, use BACK of this form.)

INVOICED

() observe this plugging:

DATE 2-11-87

INV. NO. 16116

2-10-87
FEB 10 1987
Signed Mesher Uruk
CONSERVATION DIVISION (TECHNICIAN)
Wichita, Kansas