

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24215-00-00  
Spot: S2NWSWSW Sec/Twnshp/Rge: 26-14S-16W  
866 feet from S Section Line, 5034 feet from E Section Line  
Lease Name: HEYL Well #: 6  
County: ELLIS Total Vertical Depth: 3390 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3340		
SURF	8.625	928	0	200 SX
PROD	5.5	3388	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2011 9:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: 09-19-2011 - Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel spacer.  
09-20-2011 - Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/20/2011 11:20 AM KCC Agent: PAT STAAB

Actual Plugging Report:

09-19-2011 - Witnessed by Richard Williams.  
Perforated 885'.  
Ran tubing 2900'. Allied pumped 12 sxs gel - followed with 75 sxs cement with 200# hulls.  
Pulled tubing to 960'. Allied pumped 375 sxs cement with 300# hulls - on vacuum.  
Will tag cement in the morning.  
09-20-2011 - Witnessed by Pat Staab.  
Ran tubing - tagged cement at 980'.  
Pulled to 930'. Allied pumped 235 sxs cement - circulated cement out 5 1/2" casing and 8 5/8".  
PTOH. Topped 5 1/2" casing off with 40 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3328	3333		
3252	3256		
3214	3218		


RECEIVED  
SEP 23 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

Form CP-2/3

9/29/11

SEP 21 2011