

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21041-00-00
Spot: NWSENV Sec/Twnshp/Rge: 21-9S-18W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: STAHL Well #: 2
County: ROOKS Total Vertical Depth: 3591 feet

Operator License No.: 32278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264	0	185 SX
PROD	4.5	3589	0	750 SX

Op Name: TENGASCO, INC.

Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/13/2011 1:30 PM

Plug Co. License No.: 99977

Plug Co. Name: QUALITY OIL WELL CEMENTING

Proposal Rcvd. from: GARY WAGNER

Company: TENGASCO, INC.

Phone: (785) 625-6374

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Drilled out to 1503'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/13/2011 3:10 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1488' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.
Pulled all tubing. Topped off 4 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 100#'s with less than 1/2 barrel.

Perfs:

Top	Bot	Thru	Comments
3589	3612		ARB OH

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

9/29/11

SEP 16 2011