

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-14640-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 23-20S-11W  
2310 feet from S Section Line, 990 feet from W Section Line  
Lease Name: KASSELMAN Well #: 5  
County: BARTON Total Vertical Depth: 3288 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 308        | 0           | 130 SX   |
| PROD   | 5.5   | 3278       | 0           | 100 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2011 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Emergency plug with rig over the hole.  
Tubing stuck in the well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

09/14/2011 - Tubing stuck in the well - worked on getting tubing loose - would not come loose - decided to plug.  
09/15/2011 - Tubing loose in the well.  
Ran in tubing to perf - stacked out at 75'.  
Tied to tubing - flushed hole with water - ran back in to perf - got to 2975' - perfed there.  
Pumped 130 sxs cement with 200# hulls.  
Pulled tubing - ran in perfed at 1450' - 500' - 250'.  
Ran tubing to 1450' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 500' - circulated with 100 sxs cement - pulled tubing - tied onto casing and topped off with 20 sxs cement.  
Max. P.S.I. 100#. Shut in.

Perfs:

RECEIVED  
SEP 23 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37280.

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

Form CP-2/3

9/29/11

SEP 16 2011