

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23736-00-00
Spot: W2SESWNE Sec/Twnshp/Rge: 31-15S-13W
2310 feet from N Section Line, 1800 feet from E Section Line
Lease Name: LEO MICHAELIS TRUST Well #: 2
County: RUSSELL Total Vertical Depth: 3370 feet

Operator License No.: 32325
Op Name: POPP OPERATING, INC.
Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.875	879	0	320 SX
PROD	5.5	3367	2870	135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: POPP OPEERATING, INC. Phone: (620) 786-5514

Proposed
Plugging
Method:

Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2011 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

New well lost circulation when setting casing - decided to pull casing.
Cut casing at 2870' - pulled up and pumped 700# hulls with water - topped with 30 sxs cement.
All cement pumped with 2% c.c.
Pulled casing to 1450' - pumped 100 sxs cement with 200# hulls.
Pulled casing to 900' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 500' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 200' - circulated cement to surface with 55 sxs cement.
Pulled casing - hole stayed full.

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

9/29/11

SEP 14 2011