

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22982-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 8-30S-11W
660 feet from N Section Line, 330 feet from W Section Line
Lease Name: MEAIRS Well #: 1-8
County: BARBER Total Vertical Depth: 3859 feet

Operator License No.: 32192
Op Name: PRIDE ENERGY COMPANY, A GENERA
Address: P O BOX 701950
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2680		
CIBP		3000		
CIBP		3140		
SURF	8.625	317		WITH 250 SX CMT
DVT		2060		WITH 310 SX CMT
PROD	5.5	3850	0	WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/13/2011 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SAND TO 2550' WITH 5 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 350' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 09/13/2011 12:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND TO 2550' & 5 SX CMT. 1ST PLUG AT 700'. LOADED HOLE & THEN PUMPED 50 SX CMT. 2ND PLUG AT 350'. CIRCULATED CMT TO SURFACE WITH 85 SX CMT. PUMP 15 SX CMT DOWN BACKSIDE. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
3196	3200		TOPEKA
3184	3188		TOPEKA
3056	3060		TARKIO
2756	2768		INDIAN CAVE
2618	2626		RED EAGLE

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Steve Durrant

(TECHNICIAN)