

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23298-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 21-15S-13W  
4210 feet from S Section Line, 1630 feet from E Section Line  
Lease Name: REDETZKE Well #: 2  
County: RUSSELL Total Vertical Depth: 3354 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	433	0	175 SX CMT.
TI	2.375	3350		
PROD	5.5	3350	1503	175 SX CMT.

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/13/2011 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DAVE FUNK Company: PROSPECT OIL & GAS CORP Phone: (785) 324-0643

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Cut casing at 1503' - leaving 1847' of 5 1/2" casing in the well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/13/2011 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing at 1503'.  
Pulled casing to 1494' - pumped 70 sxs cement with 300# hulls - casing parted up high in the well.  
Screwed back into casing - pumped 45 sxs cement.  
Pulled casing to 809' - pumped 40 sxs cement.  
Pulled casing to 557' - pumped 60 sxs cement with 200# hulls.  
Pulled casing to 160' - pumped 40 sxs cement - cement circulated to cellar.  
POOH. Cellar stayed full of cement.

Perfs:

Top	Bot	Thru	Comments
3350	3354		OPEN HOLE

RECEIVED  
SEP 23 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #5092.

Plugged through: CSG

District: 04

Signed

RAO:ked

(TECHNICIAN)

CM

Form CP-2/3

9/29/11

SEP 15 2011