

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02155-00-00
Spot: NWNESE Sec/Twnshp/Rge: 13-11S-17W
2309 feet from S Section Line, 1096 feet from E Section Line
Lease Name: PEARL CRESS Well #: 3
County: ELLIS Total Vertical Depth: 3392 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6	3332		400 SX
PROD	15	168	0	400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2011 10:30 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: JEFF CRAWFORD Company: MAR-LOU OIL CO., LLC Phone: (785) 885-4570

Proposed Plugging Method: Ordered 470 sxs 60/40 pozmix - 4% gel - 800# hulls.
Drilled to 1924' - hit hard surface.
Arbuckle open hole 3387'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2011 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

The Perforators shot two hole shots at 600' - 1050' - 1550'.
Outlaw Well Service RIH with tubing to 1895'.
Swift Cementing rigged to tubing and mixed and pumped 400 sxs cement with 500# hulls to circulate cement up 6" casing.
Pulled tubing - rigged to 6" casing with a swedge and pumped 20 sxs to fill 6" casing.
Rigged to 15" casing - pumped 50 sxs cement - circulated up 6" casing.
Hole standing full.

Perfs:

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #20313.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

Form CP-2/3
9/29/11

SEP 16 2011