



15-199-20002-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1968

CONSERVATION DIVISION  
Wichita, Kansas

12-27-1968

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Gene Lay of Rine Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Lay guarantees payment of the plugging fee.

Operator's full Name: Bradley & Shaw,

Complete Address: 826 Union Center Building, Wichita, Kansas.

Lease Name: Collins Well No. 1

Location: NE-NE Sec. 5 Twp. 14 Rge. (E)(W) 42

County: Wallace Total Depth 5465 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lay was instructed to plug the well as follows:

280'-- 8 5/8" Surface casing, cement circulated with 250 Sx.

Circulate hole with heavy mud. Pull DP to 1475' and displace 80 Sx. cement thru DP. Pull DP to 400' and displace 70 Sx. cement thru DP. Pull DP, set bridge @ 20' with 1/2 sack hulls and 5 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent