



15-199-20003-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GIAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Don Jackson of Bradley-Shaw has this date requested permission to plug the following described well:

Mr. Jackson guarantees payment of the plugging fee.

Operator's full Name: Bradley-Shaw,

Complete Address: 826 Union Center Building, Wichita, Kansas.

Lease Name: Pearce Well No. 1

Location: CNE-SE Sec. 2 Twp. 11 Rge. (E)(W)41

County: Wallace Total Depth 5320 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jackson was instructed to plug the well as follows:

367'--8 5/8" Surface casing, cement circulated with 275 Sx.
12 1/4" Hole drilled to 445'. Surface casing parted @ 294'. Electric log
showed no sand section below surface pipe.

Circulate hole with heavy mud. Pull DP to 420' and displace 80 Sx.
cement thru DP. Pull DP, set plug @ 40' with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar.

Very truly yours,

Conservation Division Agent