



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Swords of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: Comet Petroleum Corporation,

Complete Address: 608 Union Center Building, Wichita, Kansas.

Lease Name: Clark-Mobil Well No. 1

Location: CNE-NE Sec. 27 Twp. 15 Rge. (E)(W) 41

County: Wallace Total Depth 5517 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Swords was instructed to plug the well as follows:

631'--8 5/8" Surface casing, cement circulated with 350 Sx.  
Top of Dakota section @ 1600'.

Circulate hole with heavy mud. Pull DP to 1825' and displace 100 Sx.  
cement thru DP. Pull DP to 650' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent