



15-199-20004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas

12-08-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parke of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Trend Exploration, Limited,

Complete Address: 600 Capital Life Center, Denver, Colorado.

Lease Name: R. Waugh Well No. 1

Location: CNE-SW Sec. 16 Twp. 14 Rge. (E)(W) 42

County: Wallace Total Depth 5600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

324'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ ~~1200~~ 1600'

Circulate hole with heavy mud. Pull DP to 1825' and displace 100 Sx.
cement thru DP. Pull DP to 425' and displace 40 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent