



15-199-20006-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1972
05-19-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Ute Production Company,

Complete Address: Box #1743, Grand Junction, Colorado.

Lease Name: Neena Development Corporation Well No. 32-41

Location: 660' WEL & 660' SNL Sec. 32 Twp. 14 Rge. (E)(W) 42

County: Wallace Total Depth 5280' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Rice was instructed to plug the well as follows:

494'--8 5/8" Surface casing, cemented with 235 Sx. (Cement did not circulate).
1155'--7 5/8" Casing cement circulated with 255 Sx. (6 3/4" Hole).

Circulate hole with heavy mud. Pull DP to 1800' and displace 110 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Fisher

Conservation Division Agent