



15-169-20135-0000

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

May 11, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Kevin Hough of Berentz Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Tutcher Oil and Gas Company

Complete Address: Box 308, Overbrook, Kansas

Lease Name: Peck Well No. 1-A

Location: 760' FSL 330' FWL NW Sec. 11 Twp. 15 Rge. 1 (E) (W)

County: Saline Total Depth: 2600'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated:

Mr. Hough was instructed to plug the well as follows:

8-5/8"-130'-150 sacks Fill hole with mud to 150'. Push plug and 1/2 sack  
hulls to 150' and cement hole with 35 sacks cement. Fill hole with mud  
to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Cement rathole with 5 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1981  
5-13-81  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

[Signature]  
Conservation Division Agent