

State of Kansas



15-169-20005-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 28, 1967

RECEIVED
JUN 1 1967
6-1-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth Nat'l Bldg., Wichita, Kansas

Lease Name: Dixon Well No. 1

Location: C SE NW Sec. 20 Twp. 15 Rge. 1 (W) X

County Saline Total Depth 2720' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 90'. Push plug and 1/4 sack hulls to 90' and
cement hole with 15 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent