



15:169-70053-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

December 21, 1971

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

*Recd  
11-1-72*

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Melland Drilling Company

Complete Address: Box 783, McPherson, Kansas 67460

Lease Name: Schwarz Well No. 1

Location: SE SE SE Sec. 27 Twp. 15 Rge. 1 ~~(S)~~ (W) X

County: Saline Total Depth 2672' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 125'. Push plug and 1/4 sack hulls to 125' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

  
Conservation Division Agent