



15-169-20044-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 20, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Casing Pulling Co., Inc. this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150, McPherson, Kansas 67460

Lease Name: King Schulz Well No. 1

Location: C W/2 W/2 SW Sec. 29 Twp. 15 Rge. 1 (S) (W) X

County: Saline Total Depth 2704' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clarke was instructed to plug the well as follows:

Push 5 1/2" plug to 2550'. Fill hole with sand to 2525' and cement with
5 sacks cement. Fill hole with mud to 140'. Set rock bridge from 140'
to 130' and cement hole with 25 sacks cement. Fill hole with mud to
40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent