

State of Kansas



15169-19039-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

MAY 2 - 1966  
5-2-66

April 28, 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Frank W. Vishnefske

Complete Address: 119 So. Santa Fe, Salina, Kansas

Lease Name: Knopf Well No. 1

Location: SE SW NW Sec. 28 Twp. 15 Rge. 1 (E) (W) X

County Saline Total Depth 2680' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 115'. Push plug and 1/4 sack hulls to 115' and  
cement hole with 20 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks.  
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent