

State of Kansas



15-169-19038-0000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

CONSERVATION DIVISION  
(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 10 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

January 2, 1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Excalibur Production, Inc.

Complete Address: P.O. Box 231, Mc Pherson, Kansas 67460

Lease Name: Peterson-Wheatley Well No. 1

Location: SW SW SW Sec. 28 Twp. 15 Rge. 1 (S) (W) X

County: Saline Total Depth 2657' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2640' and cement with 5 sacks cement.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cement hole to base of cellar with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent