



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

January 27, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Molland Drilling Company, Inc.

Complete Address: Box 783, Mc Pherson, Kansas 67460

Lease Name: Peterson Well No. 2

Location: SW SW SE Sec. 30 Twp. 15 Rge. 1 (E) (W) X

County: Saline Total Depth 2743' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 110'. Push plug and 1/4 sack hulls to 110' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Push

plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent