



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 31, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Coas this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Alpine Drilling Company

Complete Address: 800 Biting Bldg., Wichita, Kansas 67202

Lease Name: McCarty Well No. 1

Location: C SE NW Sec. 30 Twp. 15 Rge. 1 (E) (W) X

County: Saline Total Depth 2701' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

Fill hole with sand to 2675' and cement with 5 sacks cement.

Fill hole with mud to 125'. Set rock bridge from 125' to 115' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent