



15-169-20141-0000

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

August 1, 1981

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Reese Oil Company 67401

Complete Address: 415 E. Prescott, Salina, Kansas

Lease Name: Ellen M. Nelson Well No. 1

Location: 330' W 510' N 6 W 1/2 NE Sec. 30 Twp. 15 Rge. 1 (E) (W)

County: Saline Total Depth: 2743

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Brucker was instructed to plug the well as follows:

8 3/8" - 132' - cement circ. - Fill hole with mud to 130'. Push plug and 1/2 sack hulls to 130' and cement hole with 20 sacks cement. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 2 sacks cement.

Very truly yours,

Conservation Division Agent

RECEIVED -  
STATE CORPORATION COMMISSION

8-6-81  
AUG 5 1981

CONSERVATION DIVISION  
WICHITA, KANSAS