



15-169-20025-0000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GIAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

June 28, 1969

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 2 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Pat Fleuffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Fleuffe guarantees payment of the plugging fee.

Operator's full Name: Dale Reese Oil Company

Complete Address: United Bldg., Salina, Kansas

Lease Name: Mason Well No. 1

Location: C NW SW Sec. 30 Twp. 15 Rge. 1 (E) (W) X

County: Saline Total Depth 2735' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Fleuffe was instructed to plug the well as follows:

Fill hole with mud to 125'. Push plug and 1/4 sack hulls to 125' and cement

hole with 20 sacks cement through drill pipe. Fill hole with mud to 40'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rat hole and cement with 2 sacks.

Very truly yours,

  
 Conservation Division Agent