



15:16 9:00053:0000

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

March 26, 1963

RECEIVED
 CONSERVATION COMMISSION
 APR 9 1963
 4-9-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Art Lamb of Lamb Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: George Hess

Complete Address: 505 N. Charles, McPherson, Kansas

Lease Name: George Hess Well No. 1.

Location: NW NE NE Sec. 31 Twp. 15 Rge. 1 (E) (W) X

County Saline Total Depth 2710' Oil Well
washdown

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2695' and cement with 5 sacks.

Fill hole with mud to 165'. Set rock bridge from 165' to

155' and cement with 20' sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks

cement.

Very truly yours,

William J. Larson
 Conservation Division Agent