



15-169-00057-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date August 25, 1958, authorized the following plugging operation:

Operator's Full Name: George Hess et al

Complete Address: 505 N. Charles, McPherson, Kansas

Lease Name: George Hess Fee Well No. 1

Location: NW-NE-NE Sec. 31 Twp. 15 Rge. 1 (E) (W) X

County: Saline Total Depth: 2770

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 160' with heavy mud--push plug and 1/2 sack hulls to 160' and cement with 20 sacks thru drill pipe. Fill hole to 40' with heavy mud--push plug and 1/2 sack hulls to 40' and cement with 10 sacks.

Very truly yours,

Signed: [Signature] Conservation Division Agent

8-29-58